

**GOEDECKE**  
CONSTRUCTION EQUIPMENT AND SUPPLIES

**GRF**

GOEDECKE RADIUS FORM  
(GANG FORMING SYSTEM)



## FULLY ASSEMBLED AND READY TO USE

Goedecke is offering something new to help save the contractor labor in the field which in turn helps the contractor make more money at the end of the job. We are offering to pre-assemble radius gang forms built specific for each particular project. Our new Goedecke Radius Form (GRF) system is an aluminum beam system faced with new plywood.

## FEATURES

The gangs come delivered to your site completely assembled and faced with NEW MDO or HDO plyform. The plyform is a purchase item so at the end of the project the contractor removes the plyform and keeps it. The plyform can then be used by the contractor for other applications of the project or for future projects.

Aluminum beams run vertically spaced 12" o.c. and are backed with an articulated radius waler

The articulated radius waler is adjustable from a 20' radius to an 80' radius and can be spaced up to 7'0" apart

The same set of gangs can be used a wide range of radiuses and will weigh 10 to 12 pounds per sq ft.

All the gangs are delivered with new plyform therefore the finish of the concrete can be a class "A", architectural finish.

Taper ties or she-bolts (approximate ties spacing up to 40 contact sq. ft. per tie).

Walkway system and braces are included. The plank and disassembly of the gangs is by contractor.

Gangs are built with Symons steel ply filler angles on the sides which are wedge bolted together, and are made and delivered 8' wide and full height

**GOEDECKEONLINE.COM**

hello@vgoedecke.com

**(314) 652-1810**

